NOTES

1. FOR DETAILS OF 33kV PLANT HV DISTRIBUTION SWITCHBOARD THREE POSITION DISCONNECT/EARTH SWITCHES, BREAKERS AND BUS TIES REFER TO 2000-F00-SLD-EL-10002 .. -10006. FOR KEY INTERLOCKING, REFER TO KEY INTERLOCKING DIAGRAMS 2000-F00-SLD-EL-10051 .. -10055

33kV INCOMER 2
FROM PARKESTON POWER STATION
33kV OVERHEAD LINE FIM B
POLE FB42 (BY KCGM)

33kV OVERHEAD LINE
FIM B POLE FB42
RECLOSER

0 - 1

SD

NSR
ENABLING WORKS
PRIMERO
PROJECT SCOPE

F00-SR-001
PLANT 33kV HV DISTRIBUTION SWITCHROOM

F00-SW-010
PLANT 33kV HV DISTRIBUTION SWITCHBOARD

2000A

2000-F00-SLD-EL-10003 | 2000-F00-SLD-EL-10004 | 2000-F00-SLD-EL-10005

B10 B11 B12 B13 B14 B15 B16 B17 B18 B19

36kV 2000A 3~E 31.5kA FOR 3s

630A 630A 630A 630A 630A 2000A 630A 630A 630A

CONT'D FROM SHEET 1 DRG 2000-F00-SLD-EL-10001

CONT'D ON SHEET 3 DRG 2000-F00-SLD-EL-10012

F13-SW-103
2000-F00-SLD-EL-10001

G 3~ F22-GE-131
415V 250kVA

F22-SR-001
CIL4 REGEN/ELUTION
415V SWITCHROOM

F22-TR-031
33 / 0.433 kV
2500 kVA

F22-TR-030
33 / 0.433 kV
2500 kVA

ATS

400A 400A 4000A 4000A

415V 600A 3NE~ 415V 4000A 3NE~ 415V 4000A 3NE~

F22-SW-131
CIL4 REGEN/ELUTION
415V EMERGENCY SWB
2000-F22-SLD-EL-10261

F22-SW-031
CIL4 REGEN/ELUTION
415V MCC 2
2000-F22-SLD-EL-10251

F22-SW-030
CIL4 REGEN/ELUTION
415V MCC 1
2000-F22-SLD-EL-10201

F13-SR-001
SAG MILL
415V SWITCHROOM

F13-TR-002
33 / 0.433 kV
2500 kVA

250A 250A 4000A

415V 600A 3NE~ 415V 4000A 3NE~

F13-SW-102
SAG MILL
415V ESSENTIAL SWB
2000-F13-SLD-EL-10311

F13-SW-002
SAG MILL
415V MCC
2000-F13-SLD-EL-10301

33kV SPARE (2)	33kV INCOMER AND VT (2)	33kV BUS TIE (2)
FULLY EQUIPPED	-	FULLY LOAD RATED

25400kVA
33 / 3.8 / 3.8kV
33 / 3.8 / 3.8kV
33 / 0.415 / 0.415kV

F13-TR-401
SAG MILL
VSD TRANSFORMER
2000-F00-SLD-EL-10004

F13-SR-003
SAG AND BALL MILLS
HV VSD SWITCHROOM

CONT'D FROM SHEET 1
DRG 2000-F00-SLD-EL-10001

SM 3~ F13-MS-401A
10000kW
SAG MILL
MOTOR 1

SM 3~ F13-MS-401B
10000kW
SAG MILL
MOTOR 2

G 3~ F16-GE-001
11kV 2500kVA

F16-TR-011
33 / 11 kV
10000 kVA

F16-SR-001
FLOTATION
11kV SWITCHROOM

ATS

630A 1250A 1250A

11kV 1250A 3E~ 11kV 1250A 3E~

630A

F16-SW-011
FLOTATION 11kV SWITCHBOARD
2000-F16-SLD-EL-10001

G 3~ F16-GE-104
415V 250kVA

F16-SR-002
FLOTATION
415V SWITCHROOM

F16-TR-004
33 / 0.433 kV
2500 kVA

F16-TR-005
33 / 0.433 kV
2500 kVA

F16-TR-008
11 / 0.433 kV
630 kVA

400A 400A 4000A 1000A

415V 600A 3NE~ 415V 4000A 3NE~ 415V 4000A 3NE~ 415V 1000A 3NE~

F16-SW-104
FLOTATION
415V ESSENTIAL SWB
2000-F16-SLD-EL-10251

F16-SW-004
FLOTATION
415V MCC
2000-F16-SLD-EL-10201

F16-SW-005
FLOTATION BLOWERS
415V MCC
2000-F16-SLD-EL-10211

F16-SW-008
FLOTATION
415V EMERGENCY SWB
2000-F16-SLD-EL-10221

2000-F00-SLD-EL-10011_Rev3

Single line diagram sheet 2