F13-SR-005
415V MILL CHILLERS & REAGENTS SWITCHROOM

F13-SW-020
MILL CHILLERS & REAGENTS 415V MOTOR CONTROL CENTRE

CONTINUED ON SHT 2
2000-F13-SLD-EL-10702

CONTINUED ON SHT 4
2000-F13-SLD-EL-10704

415V 3NE~ 50Hz 4000A 65kA for 1sec

2R-10	03R-14	03F-01	03F-04	03F-07	03F-10	03F-13	3F-05	3F-08	3F-11	3F-14	3F-17
20A	100A	20A	20A	20A	20A	20A	20A	20A	20A	20A	20A
2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A
	I > 70A										
	EOL										
I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A	I > 100/1A
M 3~	M 3~	M 3~	M 3~	M 3~	M 3~	M 3~	M 3~	M 3~	M 3~	M 3~	M 3~
1.5kW	30kW	2.2kW	2.2kW	2.2kW	1.1kW	1.1kW	0.37kW	0.37kW	0.37kW	0.37kW	0.37kW
F72-PP-696	F72-PS-418	F72-PP-661	F72-PP-662	F72-PP-663	F72-PP-664	F72-PP-665	F72-PP-666	F72-PP-667	F72-PP-668	F72-PP-669	F72-PP-670
THICKENERS STANDBY FLOCCULANT DOSING PUMP	FLOCCULANT AREA SUMP PUMP	PAX DOSING PUMP 1	PAX DOSING PUMP 2	PAX DOSING PUMP 3	PAX DOSING PUMP 4	PAX DOSING PUMP 5	FROTHER DOSING PUMP 1	FROTHER DOSING PUMP 2	FROTHER DOSING PUMP 3	FROTHER DOSING PUMP 4	FROTHER DOSING PUMP 5
2000-F72-SCM-EL-10712	2000-F72-SCM-EL-10713	2000-F72-SCM-EL-10202	2000-F72-SCM-EL-10203	2000-F72-SCM-EL-10204	2000-F72-SCM-EL-10205	2000-F72-SCM-EL-10206	2000-F72-SCM-EL-10251	2000-F72-SCM-EL-10252	2000-F72-SCM-EL-10253	2000-F72-SCM-EL-10254	2000-F72-SCM-EL-10255

NOTES

1. REFER TO SHEET 1.

LEGEND

1. REFER TO SHEET 1.

NORTHERN STAR RESOURCES

Approved	X
Approved as Noted	
Not Approved	
For Information Only	

ACCEPTANCE DOES NOT RELIEVE THE SUPPLIER / CONTRACTOR OF ITS RESPONSIBILITY OR LIABILITIES UNDER THE PURCHASE ORDER / CONTRACT

2000-F13-SLD-EL-10703_Rev1

Milling & classification F13-SW-020 415V MCC single line diagram sheet 3

30MAY25 8:08AM SANDRA CULL