F21-SR-001
415V CIL4 SWITCHROOM

F21-SW-006
CIL4 415V MOTOR CONTROL CENTRE No.1

CONTINUED ON SHT 1
2000-F21-SLD-EL-10201

CONTINUED ON SHT 3
2000-F21-SLD-EL-10203

EMERGENCY BUS 415V 3NE~ 50Hz 4000A 65kA for 1sec

02F-01	02F-09	06R-10	06R-18	02F-17	02F-21	06R-05	02R-10	02R-15	02R-20
250A	250A	250A	250A	160A	160A	100A	100A	100A	100A
2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A
90A	90A	90A	90A	100/1A	100/1A	70A	70A	70A	70A
EOL	EOL	EOL	EOL			EOL	EOL	EOL	EOL
F21-SC-413A CIL4 TANK 3 INTERTANK SCREEN 1 2000-F21-SCM-EL-10230	F21-SC-413B CIL4 TANK 3 INTERTANK SCREEN 2 2000-F21-SCM-EL-10231	F21-SC-414A CIL4 TANK 4 INTERTANK SCREEN 1 2000-F21-SCM-EL-10232	F21-SC-414B CIL4 TANK 4 INTERTANK SCREEN 2 2000-F21-SCM-EL-10233	F21-PP-470 CIL4 LOADED CARBON PUMP 2000-F21-SCM-EL-10218	F21-PP-471 CIL4 CARBON TRANSFER PUMP 1 2000-F21-SCM-EL-10219	F21-PP-472 CIL4 CARBON TRANSFER PUMP 2 2000-F21-SCM-EL-10220	F21-PP-473 CIL4 CARBON TRANSFER PUMP 3 2000-F21-SCM-EL-10221	F21-PP-474 CIL4 CARBON TRANSFER PUMP 4 2000-F21-SCM-EL-10222	F21-PP-475 CIL4 CARBON TRANSFER PUMP 5 2000-F21-SCM-EL-10223
75kW	75kW	75kW	75kW	55kW	55kW	30kW	30kW	30kW	30kW

1

NOTES

1. REFER TO SHEET 1.

LEGEND

1. REFER TO SHEET 1.

NORTHERN STAR RESOURCES LIMITED

Approved	[X]
Approved as Noted	[ ]
Not Approved	[ ]
For Information Only	[ ]

Signed [redacted] Date 19/11/2025

ACCEPTANCE DOES NOT RELIEVE THE SUPPLIER / CONTRACTOR OF ITS RESPONSIBILITY OR LIABILITIES UNDER THE PURCHASE ORDER / CONTRACT

2000-F21-SLD-EL-10202_Rev1

Flotation tailings CIL4 F21-SW-006 415V MCC single line diagram sheet 2

O:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\23517 KCGM GROWTH PROJECT\03 DELIVERABLES\EL\F21 - FLOTATION TAILINGS CIL 4\2000-F21-SLD-EL-10202.DWG 06NOV25 11:07AM HOTSEAT04