240VAC UPS SUPPLY
FROM IN F13-DB-202
2000-F13-TLD-EL-10022

240VAC 1 — F13DCS403P1-L — 240VAC 2
240VAC 3 — F13DCS403P1-N — 240VAC 4

Q006 10A — 0060 — F13DCS403-PS1
PHOENIX
QUINT4-PS/1AC/24DC/20
240VAC/24VDC, 20A POWER SUPPLY
DC OK 13 — F13DCS403PS1+24VDC
DC OK 14 — F13DCS403PS1
POWER SUPPLY 1
24VDC HEALTHY
TO 2000-F13-TER-IC-10032

Q007 10A — 0076 — F13DCS403-PS2
PHOENIX
QUINT4-PS/1AC/24DC/20
240VAC/24VDC, 20A POWER SUPPLY
DC OK 13 — F13DCS403PS1+24VDC
DC OK 14 — F13DCS403PS1
POWER SUPPLY 2
24VDC HEALTHY
TO 2000-F13-TER-IC-10032

(+24VDC) 0131 (0VDC)
(+24VDC) 0137 (0VDC)
0130
0138

F13DCS403-RM
PHOENIX
QUINT-ORING/24DC/2X20/1X40
REDUNDANCY MODULE

(+24VDC) (0VDC)
Q022 20A

0220 — 0205

Q025 6A — 0250 — S025 DOOR — 0255 — WH — 0VDC 1 — PANEL LIGHT

FIELD CONTROL UNIT
Q028 6A — 0280 — POWER SUPPLY 1 — 0VDC 2 — F13-FCS-403
Q029 6A — POWER SUPPLY 2 — 0VDC 3
FIELD CONTROL UNIT
24VDC POWER SUPPLIES

Q032 6A — 0VDC 4 — SPARE
24VDC POWER SUPPLY

Q034 6A — 0VDC 5 — SPARE
24VDC POWER SUPPLY

Q036 2A — 0VDC 6 — SPARE
24VDC POWER SUPPLY

Q038 2A — 0380 — F13SR002-LCS 2000-F13-TER-EL-10902 — 0VDC 7
F13SR002-LCS
SWITCHROOM
EMERGENCY SHUTDOWN
24VDC POWER SUPPLY

2

0220 — 24VDC SUPPLY CONT'D ON LINE 51 — 0205

(+24VDC) — 0220 — 24VDC SUPPLY CONT'D FROM LINE 048 — 0205 — (0VDC)

Q053 10A — 0530 — POWER SUPPLY 1 — 0VDC 8
Q054 10A — 0540 — POWER SUPPLY 2 — 0VDC 9
NODE INTERFACE UNIT F13FCS403-NU01
YOKOGAWA - NIU
NETWORK I/O NODE
A2NN30D-440001102

Q060 10A — 0600 — 24VDC FIELD POWER 2000-F13-TER-IC-10032
FIELD POWER - I/O BASE PLATE
16 CHANNEL I/O MODULE F13FCS403NU01-01 DIGITAL INPUT
0VDC 10 — 16 CHANNEL NIO BASEPLATE A2BN3D-01020/L

Q065 10A — 0650 — 24VDC FIELD POWER 2000-F13-TER-IC-10033
FIELD POWER - I/O BASE PLATE
16 CHANNEL I/O MODULE F13FCS403NU01-02 DIGITAL INPUT
0VDC 11 — 16 CHANNEL NIO BASEPLATE A2BN3D-01020/L

Q070 10A — 0700 — 24VDC FIELD POWER 2000-F13-TER-IC-10034
FIELD POWER - I/O BASE PLATE
16 CHANNEL I/O MODULE F13FCS403NU01-03 ANALOGUE INPUT
0VDC 12 — 16 CHANNEL NIO BASEPLATE A2BN3D-01020/L

NOTES

1. TERMINALS ON TERMINAL STRIPS ABOVE 50VAC SHALL HAVE A SEPARATE PERSPEX SHROUD AND SHALL BE LABELLED "DANGER xxxVAC".
2. WIRE NUMBER FERRULES ON TERMINAL STRIP SHALL BE PREFIXED WITH EQUIPMENT NUMBER e.g. F13DCS403-xxxx.
3. EACH WIRE SHALL BE IDENTIFIED AT BOTH ENDS WITH FERRULES.
4. FOR NETWORK CONNECTION & BUS CABLING DETAILS REFER TO DCS PANEL COMMUNICATIONS TERMINATION DIAGRAMS.
5. INSTRUMENT EARTH BAR TO BE BONDED TO MAIN EARTH BAR WITH SOLID COPPER LINK.

LEGEND

- FIELD TERMINAL
- DCS OR I/O TERMINAL
- 0VDC TERMINAL FOR 24VDC (2)
- DEVICE TERMINAL
- EARTH BAR
- INSTRUMENT EARTH BAR

NIO BASEPLATE

F13FCS403NU01-01
- NETWORKED INPUT/OUTPUT (N-IO) BASEPLATE
- NODE INTERFACE UNIT (N-IU)
- FIELD CONTROL UNIT

DRG No.	REFERENCES
2000-F13-TLD-EL-10022	F13-DB-202 BALL MILL LV SWITCHROOM 240VAC UPS DB THREE LINE DIAGRAM
2000-F13-DRG-IC-10031	F13-DCS-403 415V SWITCHROOM DCS PANEL GENERAL ARRANGEMENT
2000-F13-TER-IC-10031	F13-DCS-403 415V SWITCHROOM DCS PANEL COMMUNICATIONS TERMINATION DIAGRAM
2000-F13-TER-IC-10032	F13-DCS-403 415V SWITCHROOM DCS PANEL TERMINATION DIAGRAM SHEET 1 (TO SHEET 3 - 10034)
2000-F13-STD-EL-10001	GENERAL NOTES AND STANDARD DRAWINGS INDEX

REV	DATE	DESCRIPTION
2	01APR25	FAT REDLINES INCORPORATED
1	12DEC24	ADDED E-SHUT LCS
0	30AUG24	APPROVED FOR CONSTRUCTION

[redacted]
DRAW | CHECK | DESIGN | TECH APP | PROJ APP

NORTHERN STAR RESOURCES LIMITED

PRIMERO
primero.com.au | DESIGN | CONSTRUCT | OPERATE
PRIMERO PROJECT NUMBER: 23517

INFORMATION AND REPRESENTATIONS ON THIS DRAWING ARE THE INTELLECTUAL PROPERTY OF PRIMERO UNLESS SPECIFICALLY IDENTIFIED OTHERWISE. ALL RIGHTS INCLUDING USE RESERVED

PROJECT: NORTHERN STAR RESOURCES LTD
KCGM GROWTH PROJECT

TITLE: MILLING & CLASSIFICATION - F13-SR-002
F13-DCS-403 415V SWITCHROOM DCS PANEL
SCHEMATIC DIAGRAM

SHEET	SCALE	DRG No.	REVISION
A1	NONE	2000-F13-SCM-IC-10031	2

O:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\23517 KCGM GROWTH PROJECT\03 DELIVERABLES\IC\F13 - MILLING & CLASSIFICATION\2000-F13-SCM-IC-10031.DWG 01APR25 3:21PM MARIECRIS.SANTOS