F13-SR-004
415V RECYCLE CRUSHING SWITCHROOM

F13-SW-014
RECYCLE CRUSHING 415V MOTOR CONTROL CENTRE

CONTINUED ON SHT 2
2000-F13-SLD-EL-10402

CONTINUED ON SHT 4
2000-F13-SLD-EL-10404

415V 3NE~ 50Hz 4000A 65kA for 1sec

4F-01 20A 2A 32A
2R-21 32A 2A 32A
3F-21 32A 2A 32A
3R-04 32A 2A 32A
4R-09 20A 2A 32A
5R-09 20A 2A 32A
4F-16 20A 2A 32A
2R-01 32A 2A 32A
2R-05 32A 2A 32A
3F-01 32A 2A 32A
3F-05 32A 2A 32A

/ > 100A

/ > 70A

EOL

NOTE 10

JB

M 3~ 4.8kW — F13-FV-402
RECYCLE CRUSHER D
FEEDER
2000-F13-SCM-EL-10417

M 3~ 4.8kW

4x2kW — F13-HT-403/404/451/452
RECYCLE CRUSHER C
LUBRICATION
HEATER 1 - 4
2000-F13-SCM-EL-10418

4x2kW — F13-HT-405/406/453/454
RECYCLE CRUSHER D
LUBRICATION
HEATER 1 - 4
2000-F13-SCM-EL-10419

M 3~ 11kW — F13-HU-405
RECYCLED CRUSHER C
FEED BIN ISOLATION GATE
HYDRAULIC UNIT
2000-F13-SCM-EL-10420

M 1~ 0.8 kW — F13-LU-451
COARSE ORE
RECLAIM FEEDER 1
AUTOLUBE GREASE SYSTEM
2000-F13-SCM-EL-10438

M 1~ 0.8 kW — F13-LU-452
COARSE ORE
RECLAIM FEEDER 2
AUTOLUBE GREASE SYSTEM
2000-F13-SCM-EL-10439

M 1~ 0.8 kW — F13-LU-453
EMERGENCY FEEDER
AUTOLUBE GREASE SYSTEM

2000-F13-SCM-EL-10440

M 3~ 11kW — F13-PO-401
RECYCLE CRUSHER C
LUBRICATION PUMP 1

2000-F13-SCM-EL-10421

M 3~ 11kW — F13-PO-402
RECYCLE CRUSHER C
LUBRICATION PUMP 2

2000-F13-SCM-EL-10422

M 3~ 11kW — F13-PO-406
RECYCLE CRUSHER D
LUBRICATION PUMP 1

2000-F13-SCM-EL-10423

M 3~ 11kW — F13-PO-407
RECYCLE CRUSHER D
LUBRICATION PUMP 2

2000-F13-SCM-EL-10424

NOTES

1. REFER TO SHEET 1.

LEGEND

1. REFER TO SHEET 1.

2000-F13-SLD-EL-10403_Rev2

Recycle crushing F13-SW-014 415V MCC single line diagram sheet 3

O:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\235177 KCGM GROWTH PROJECT\03 DELIVERABLES\ELV\F13 - MILLING & CLASSIFICATION\2000-F13-SLD-EL-10403.DWG 04SEP26 9:55AM GRENVILLE.DEASY