F13-SR-005
415V MILL CHILLERS & REAGENTS SWITCHROOM

F13-SW-020
MILL CHILLERS & REAGENTS 415V MOTOR CONTROL CENTRE

CONTINUED ON SHT 3
2000-F13-SLD-EL-10103

415V 3NE~ 50Hz 4000A 65kA for 1sec

3R-08	3R-12	3R-16	03R-04	03R-07	3R-20	3F-20	03F-20	02R-13
20A	20A	20A	xxxA	xxxA	100A	100A	100A	20A
2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A
100/1A	100/1A	100/1A	xxxA	xxxA	70A	70A	70A	70A
					EOL	EOL	EOL	EOL
M 3~ 0.55kW F72-PP-671 COPPER SULPHATE DOSING PUMP 1 2000-F72-SCM-EL-10301	M 1~ 0.017kW F72-FN-671 COPPER SULPHATE DOSING PUMP 1 MOTOR COOLING FAN 2000-F72-SCM-EL-10301	M 3~ 0.55kW F72-PP-672 COPPER SULPHATE DOSING PUMP 2 2000-F72-SCM-EL-10302	M 1~ 0.017kW F72-FN-672 COPPER SULPHATE DOSING PUMP 2 MOTOR COOLING FAN 2000-F72-SCM-EL-10302	M 3~ 0.37kW F72-PP-679 COPPER SULPHATE DOSING PUMP 3 2000-F72-SCM-EL-10303	M 1~ 0.017kW F72-FN-679 COPPER SULPHATE DOSING PUMP 3 MOTOR COOLING FAN 2000-F72-SCM-EL-10303	M 3~ 2.2kW F72-PP-712 CONCENTRATE BELT FILTER 1 FLOCC DOSING PUMP 2000-F72-SCM-EL-10714 FUTURE	M 3~ 2.2kW F72-PP-713 CONCENTRATE BELT FILTER 2 FLOCC DOSING PUMP 2000-F72-SCM-EL-10715 FUTURE	M 3~ 30kW F72-PS-420 COPPER SULPHATE AREA SUMP PUMP 2000-F72-SCM-EL-10717	M 3~ 30kW F72-PS-425 FROTHER AREA SUMP PUMP 2000-F72-SCM-EL-10257	30kW SPARE DOL 2000-F72-SCM-EL-10207	M 1~ 2.2kW F72-XM-441 FLOCCULENT SILO DEHUMIDIFIER 2000-F72-SCM-EL-10719

LOAD MOVED TO SHEET 1

NOTES

1. REFER TO SHEET 1.

LEGEND

1. REFER TO SHEET 1.

Approved	X
Approved as Noted	
Not Approved	
For Information Only	

Signed [redacted] Date 24.06.2025

ACCEPTANCE DOES NOT RELIEVE THE SUPPLIER / CONTRACTOR OF ITS RESPONSIBILITY OR LIABILITIES UNDER THE PURCHASE ORDER / CONTRACT

2000-F13-SLD-EL-10704_Rev1

Milling & classification F13-SW-020 415V MCC single line diagram sheet 4

O:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\23517 KCOM GROWTH PROJECT\03 DELIVERABLES\ELF\F13 - MILLING & CLASSIFICATION\2000-F13-SLD-EL-10704.DWG 30MAY25 8:08AM SANDRA CULL