F13-SW-103
2000-F13-SLD-EL-10911

F13-SR-001
415V SAG MILL SWITCHROOM

SWR EARTH BAR

FEEDER FROM F13-SW-002
2000-F13-SLD-EL-10301

TO F13-SW-002
2000-F13-SLD-EL-10301

F13-SW-102
SAG MILL 415V ESSENTIAL SWITCHBOARD

EARTH BAR

NEUTRAL BAR
NOTE 1

AFD

2A
63A

2A
63A

MANUAL
MCCB CHANGEOVER
SWITCH 3 POLE 630A

00F-05

415V 3NE~ 50Hz 630A 65kA for 1sec

INC

01F-16 160A 2A 32A 90A 160A 250A
01F-05 32A 2A 32A 70A 32A 32A
01F-21 250A 2A 32A 90A
01F-12 100A 2A 32A 70A ECR
01F-09 63A 2A 32A 70A
02F-16 250A 2A 32A 90A
02F-11 250A 2A 32A 90A 160A 250A
02F-06 250A 2A 32A 90A 160A 250A

69kW
F13-DB-001
SAG MILL
415V SWITCHROOM
L&SP DB
2000-F13-SCM-EL-10305

ISL
F13UPS001-ISL
240VAC UPS
MAINTENANCE
BYPASS SWITCH
2000-F13-SCM-EL-10306

10kW
F13-DB-201
SAG MILL
415V SWITCHROOM
240VAC UPS DB
2000-F13-TLD-EL-10012

UPS
10kW
F13-UPS-001
SAG MILL
415V SWITCHROOM
240VAC UPS
2000-F13-TLD-EL-10012

69kW
F13-DB-304
MILLING AREA 1
L&SP DB
2000-F13-SCM-EL-10307

CR
48kW
F13-CR-402
CLASSIFICATION AREA
OVERHEAD CRANE
2000-F13-SCM-EL-10308

CR
15.9kW
F13-CR-411
MILL LINER
MAINTENANCE HOIST 1
2000-F13-SCM-EL-10309

69kW
F13-DB-307
MILLING AREA 4
L&SP DB
2000-F13-SCM-EL-10364

69kW
F13-DB-308
MILLING AREA 5
L&SP DB
2000-F13-SCM-EL-10973

69kW
F13-DB-003
SAG & BALL MILL
VSD SWITCHROOM
L&SP DB
2000-F13-SCM-EL-10906

NOTES

1. EARTH-NEUTRAL LINK INSTALLED IN UPSTREAM F13-SW-002 INCOMER TIER. SIGNAGE SHALL BE PLACED ON F13-SW-102 SWITCHBOARD READING "M.E.N. LINK LOCATED IN F13-SW-002 INCOMER TIER"
2. SWITCHBOARD SHALL BE EXTENSIBLE AND BE PROVIDED WITH THE FACILITY TO EXTEND THE MAIN BUSBAR AND APPEND ADDITIONAL TIERS AT ONE END WITHOUT MAJOR STRUCTURAL DISASSEMBLY.
3. MINIATURE CIRCUIT BREAKERS SHALL BE SIZED AND RATED TO SUIT ACB AND INCOMER REQUIREMENTS.
4. CIRCUIT BREAKER TO BE SUBSTITUED FOR FUSED-SWITCH WHERE REQUIRED BY EQUIPMENT MANUFACTURERS GUIDELINES.

LEGEND

- PFR — PHASE FAILURE RELAY
- / > — EARTH LEAKAGE RELAY
- xxxA / xxxA — ST TRIP SET POINT / CB SIZE
- AFD — ARC FLASH DETECTION
- ECR — EARTH CONTINUITY RELAY

NORTHERN STAR RESOURCES LIMITED

Approved	X
Approved as Noted	
Not Approved	
For Information Only	

Signed [redacted] Date 15/09/2025

ACCEPTANCE DOES NOT RELIEVE THE SUPPLIER / CONTRACTOR OF ITS RESPONSIBILITY OR LIABILITIES UNDER THE PURCHASE ORDER / CONTRACT

DRG No.	REFERENCES
2000-F13-SCM-EL-10304	F13-SW-002 415V MCC ARC FLASH SYSTEM SCHEMATIC DIAGRAM
2000-F13-SCM-EL-10303	F13-SW-002 415V MCC 24VDC DISTRIBUTION SCHEMATIC DIAGRAM
2000-F13-SCM-EL-10354	F13-SW-102 415V ESSENTIAL SWITCHBOARD INCOMER SCHEMATIC DIAGRAM
2000-F13-DRG-EL-10101	F13-SR-001 415V SWITCHROOM ELECTRICAL EQUIPMENT LAYOUT
2000-F13-BLK-IC-10001	F13-SR-001 415V SWITCHROOM AND REMOTE I/O COMMUNICATIONS BLOCK DIAGRAM
2000-F13-SLD-EL-10301	F13-SW-002 415V MCC SINGLE LINE DIAGRAM SHEET 1
2000-F00-SLD-EL-10002	F00-SW-010 33kV SWITCHBOARD SINGLE LINE DIAGRAM SHEET 1 OF 5
2000-F00-STD-EL-10001	GENERAL NOTES AND STANDARD DRAWINGS INDEX

REV	DATE	DESCRIPTION	DRAW	CHECK	DESIGN	TECH APP	PROJ APP
1	18AUG25	FAT REDLINES INCORPORATED					
0	29AUG24	APPROVED FOR CONSTRUCTION					

NORTHERN STAR RESOURCES LIMITED

INFORMATION AND REPRESENTATIONS ON THIS DRAWING ARE THE INTELLECTUAL PROPERTY OF PRIMERO UNLESS SPECIFICALLY IDENTIFIED OTHERWISE. ALL RIGHTS INCLUDING USE RESERVED

PRIMERO
primero.com.au | DESIGN | CONSTRUCT | OPERATE

PRIMERO PROJECT NUMBER: 23517

PROJECT: NORTHERN STAR RESOURCES LTD
KCGM GROWTH PROJECT

TITLE: MILLING & CLASSIFICATION - SAG MILL
F13-SW-102 415V ESSENTIAL SWITCHBOARD
SINGLE LINE DIAGRAM

SHEET	SCALE	DRG No.	REVISION
A1	NONE	2000-F13-SLD-EL-10311	1

D:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\23517 KCGM GROWTH PROJECT\03 DELIVERABLES\E\LV\F13 - MILLING & CLASSIFICATION\2000-F13-SLD-EL-10311.DWG 27AUG25 7:52AM HOTSEAT04