F13-SR-001
415V SAG MILL SWITCHROOM

F13-SW-002
SAG MILL 415V MOTOR CONTROL CENTRE

CONTINUED ON SHT 1
2000-F13-SLD-EL-10301

CONTINUED ON SHT 3
2000-F13-SLD-EL-10303

415V 3NE~ 50Hz 4000A 65kA for 1sec

1F-17 50A 2A 32A 70A EOL
4.8kW
F13-HT-421
SAG MILL
MOTOR 1
ANTI CONDENSATION HEATER
2000-F13-SCM-EL-10349

4.8kW
F13-HT-425
SAG MILL
MOTOR 2
ANTI CONDENSATION HEATER
2000-F13-SCM-EL-10349

6R-16 50A 2A 32A 70A EOL
1kW
F13-HT-408
SAG MILL
MOTOR LUBE UNIT
HEATER
2000-F13-SCM-EL-10322

5R-01 63A 2A 32A 70A EOL
2x10kW
F13-HT-433/434
SAG MILL
LUBE OIL RETURN COMP.
HEATER 1 & 2
2000-F13-SCM-EL-10323

5R-05 63A 2A 32A 70A EOL
2x10kW
F13-HT-435/436
SAG MILL
LUBE OIL CONDITIONED COMP.
HEATER 3 & 4
2000-F13-SCM-EL-10325

1

5F-01 63A 2A 32A 70A ECR
DPS
63A
F13-DPS-001
SAG MILL
BOLT HAMMER
DECONTACTOR PANEL 1
2000-F13-SCM-EL-10328

5F-05 63A 2A 32A 70A ECR
DPS
63A
F13-DPS-002
SAG MILL
BOLT HAMMER
DECONTACTOR PANEL 2
2000-F13-SCM-EL-10329

5F-09 63A 2A 32A 70A ECR
DPS
63A
F13-DPS-003
SAG MILL
BOLT HAMMER
DECONTACTOR PANEL 3
2000-F13-SCM-EL-10350

5F-13 63A 2A 32A 70A ECR
DPS
63A
F13-DPS-004
SAG MILL
BOLT HAMMER
DECONTACTOR PANEL 4
2000-F13-SCM-EL-10351

5F-17 63A 2A 32A 70A ECR
DPS
63A
F13-DPS-005
SAG MILL
BOLT HAMMER
DECONTACTOR PANEL 5
2000-F13-SCM-EL-10356

5F-21 63A 2A 32A 70A ECR
DPS
63A
F13-DPS-006
SAG MILL
BOLT HAMMER
DECONTACTOR PANEL 6
2000-F13-SCM-EL-10357

1

NOTES

1. REFER TO SHEET 1.

LEGEND

1. REFER TO SHEET 1.

NORTHERN STAR RESOURCES LIMITED

Approved	X
Approved as Noted	
Not Approved	
For Information Only	

ACCEPTANCE DOES NOT RELIEVE THE SUPPLIER / CONTRACTOR OF ITS RESPONSIBILITY OR LIABILITIES UNDER THE PURCHASE ORDER / CONTRACT

2000-F13-SLD-EL-10302_Rev1

SAG mill F13-SW-002 415V MCC single line diagram sheet 2

O:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\23517 KCGM GROWTH PROJECT\03 DELIVERABLES\E\L\F13 - MILLING & CLASSIFICATION\2000-F13-SLD-EL-10302.DWG 28AUG25 1:30PM HOTSEAT04