F13-SR-002
415V BALL MILL SWITCHROOM

F13-SW-003
BALL MILL 415V MOTOR CONTROL CENTRE

CONTINUED ON SHT 3
2000-F13-SLD-EL-10903

CONTINUED ON SHT 5
2000-F13-SLD-EL-10905

415V 3NE~ 50Hz 4000A 65kA for 1sec

4F-01	5F-01	8R-15	6F-14	8R-01	8R-07	8R-11	6R-01	6R-05	8F-17	4R-09	4R-13
20A	20A	400A	100A	32A	50A	50A	50A	50A	63A	20A	630A
2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A	2A 32A
70A	70A	100/1A	70A	70A	70A	70A	70A	70A	70A	70A	100/1A
EOL	EOL	EOL	EOL	EOL	EOL	EOL	EOL	EOL	ECR	EOL	EOL

1

F13-PO-534	F13-PO-535	F13-PP-403	F13-PS-409	F13-SC-403	F13-SL-401	F13-SL-402	F13-SL-403	F13-SL-404	F13-XM-404	F14-AG-410	F14-CO-401
M 3~	M 3~	t° M 3~	M 3~	M 3~ M 3~	M 3~	M 3~	M 3~	M 3~	CP 1	M 3~	t° M 3~
1.5kW	1.5kW	110kW	30kW	9.62kW	11kW	11kW	11kW	11kW	63A	2.2kW	220kW
BALL MILL PINION BEARING LUBE OIL PUMP 1	BALL MILL PINION BEARING LUBE OIL PUMP 2	TRASH DEWATERING SCREEN UNDERFLOW PUMP	TRASH SCREEN AREA SUMP PUMP	TRASH DEWATERING SCREEN	TRASH SCREEN 1	TRASH SCREEN 2	TRASH SCREEN 3	TRASH SCREEN 4	MILL FEED SPOUT TRANSPORTER	INTENSIVE CYANIDE LEACH REACTOR SOLUTION TANK AGITATOR	GRAVITY CONCENTRATOR 1
2000-F13-SCM-EL-10938	2000-F13-SCM-EL-10939	2000-F13-SCM-EL-10501	2000-F13-SCM-EL-10502	2000-F13-SCM-EL-10503	2000-F13-SCM-EL-10504	2000-F13-SCM-EL-10505	2000-F13-SCM-EL-10506	2000-F13-SCM-EL-10507	2000-F13-SCM-EL-10508	2000-F14-SCM-EL-10201	2000-F14-SCM-EL-10202

NOTES

1. REFER TO SHEET 1.

LEGEND

1. REFER TO SHEET 1.

NORTHERN STAR RESOURCES LIMITED

Approved	X
Approved as Noted	
Not Approved	
For Information Only	

ACCEPTANCE DOES NOT RELIEVE THE SUPPLIER / CONTRACTOR OF ITS RESPONSIBILITY OR LIABILITIES UNDER THE PURCHASE ORDER / CONTRACT

2000-F13-SLD-EL-10904_Rev1

Ball mill F13-SW-003 415V MCC single line diagram sheet 4

O:\CAD PROJECTS\235 NORTHERN STAR RESOURCES LTD\23517 KCGM GROWTH PROJECT\03 DELIVERABLES\ELV\F13 - MILLING & CLASSIFICATION\2000-F13-SLD-EL-10904.DWG 25SEP25 12:52PM HOTSEAT04