SUBSTATION No.68

VARIABLE SPEED DRIVE 30-VS-62A

REF. DRG. 2000-F30-TER-IC-10465

IT 30744A

X6

11	30744A-1	2W
12	30744A-2	2Bk

PART OF 30VS62A-N1

DCS 30-PC-62

REFER DRAWING 2000-F30-TER-IC-10486

CABINET AR

TS A

2W	43	30744A-1	A
2Bk	44	30744A-2	B +
			C –

IT 30744A	
ANALOG INPUT AAM11	
DOMAIN	02
FCS	05
ADDRESS: %Y	
NODE (01-08)	06
IOU (1-5)	2
SLOT (1-4)	1
CHANNEL (1-16)	07

II 30744A

LOOP 30744A - CIL 2 OXYGEN INJECTION
PUMP 1 F30TK32A-PP01, MOTOR CURRENT

VARIABLE SPEED DRIVE 30-VS-62B

REF. DRG. 30\E\1051-014

IT 30744B

X6

1	30744B-1	2W
2	30744B-2	2Bk

PART OF 30VS62B-N1

DCS 30-PC-62

REFER DRAWING 30-E-0565

CABINET AR

TS A

2W	48	30744B-1	A
2Bk	49	30744B-2	B +
			C –

IT 30744B	
ANALOG INPUT AAM11	
DOMAIN	01
FCS	05
ADDRESS: %Z	
NODE (01-08)	06
IOU (1-5)	2
SLOT (1-4)	1
CHANNEL (1-16)	08

II 30744B

LOOP 30744B - TAILINGS DISPOSAL
PUMP No.2 30-PP-62B MOTOR CURRENT

VARIABLE SPEED DRIVE 30-VS-62C

REF. DRG. 2000-F30-TER-IC-10465

IT 30744C

X6

11	30744C-1	2W
12	30744C-2	2Bk

PART OF 30VS62C-N1

DCS 30-PC-62

REFER DRAWING 2000-F30-TER-IC-10486

CABINET AR

TS A

2W	52	30744C-1	A
2Bk	53	30744C-2	B +
			C –

IT 30744C	
ANALOG INPUT AAM11	
DOMAIN	02
FCS	05
ADDRESS: %Y	
NODE (01-08)	06
IOU (1-5)	2
SLOT (1-4)	1
CHANNEL (1-16)	09

II 30744C

LOOP 30744C - CIL 2 OXYGEN INJECTION
PUMP 2 F30TK32B-PP01 MOTOR CURRENT

IT 30744D

X21

11	30744D-1	1W
12	30744D-2	1Bk

PART OF 30PP62D-N1

DCS 30-PC-62

REFER DRAWING 30-E-0576

CABINET DR

TS M

1W	41	30744D-1	A
1Bk	42	30744D-2	B +
			C –

IT 30744D	
ANALOG INPUT AAM11	
DOMAIN	01
FCS	05
ADDRESS: %Z	
NODE (01-08)	06
IOU (1-5)	5
SLOT (1-4)	1
CHANNEL (1-16)	11

II 30744D

LOOP 30744D- TAILINGS DISPOSAL
PUMP No.4 30-PP-62D MOTOR CURRENT

4

LEGEND

CORE No./COLOUR
TERMINAL LINK
FERRULE No.
TERMINAL No.
CORE No./COLOUR

NOTES

LEGEND
- EXISTING
- NON-EXISTENT
- STAGE 1 - NEW
- STAGE 1 - REMOVE
- STAGE 1 - DECOMMISSIONED (OTHERS)
- STAGE 2 - NEW
- STAGE 2 - REMOVE
- STAGE 2 - DECOMMISSIONED (OTHERS)

KCGM GROWTH PROJECT

DRAWING NO: 2000-F30-SCM-IC-10450

REV	DATE	DESCRIPTION	CHECK	TECH APP
0	08/08/25	APPROVED FOR CONSTRUCTION	[redacted]	

CLIENT APPROVED for CONSTRUCTION

SIGNED: [redacted] DATE: 25/5/95

2000-F30-SCM-IC-10450_Rev0

Carbon in leach (CIL3) loop diagram sheet 17 schematic diagram