EQUIPMENT NAME:	**Refer to table below**
EQUIPMENT NUMBER:	**Refer to table below**

Procurement Package	"EL008" - 415V TSF Pump Control Panels & LCS	
Equipment No.	**Equipment Name**	
F75-CP-593	FIM II Cell G Underdrainage Pump Control Panel	
F75-CP-559	FIM II Cell G Toe Drain Pump 1 Control Panel	
F75-CP-560	FIM II Cell G Toe Drain Pump 2 Control Panel	
F75-CP-556	FIM III Underdrainage Pump 1 Control Panel	
F75-CP-557	FIM III Underdrainage Pump 2 Control Panel	
F75-CP-558	FIM III Toe Drain Pump Control Panel	
F75-CP-801	FIM III Seepage Pump 1 Control Panel	
F75-CP-802	FIM III Seepage Pump 2 Control Panel	
F75-CP-803	FIM III Seepage Pump 3 Control Panel	
F75-CP-804	FIM III Seepage Pump 4 Control Panel	
F75PS593-LCS	F75-PS-593 FIM II Cell G Underdrainage Pump Local Control Station	
F75PS559-LCS	F75-PS-559 FIM II Cell G Toe Drain Pump 1 Local Control Station	
F75PS560-LCS	F75-PS-560 FIM II Cell G Toe Drain Pump 2 Local Control Station	
F75PS556-LCS	F75-PS-556 FIM III Underdrainage Pump 1 Local Control Station	
F75PS557-LCS	F75-PS-557 FIM III Underdrainage Pump 2 Local Control Station	
F75PS558-LCS	F75-PS-558 FIM III Toe Drain Pump Local Control Station	
Reference Documents		
Equipment Lists		
Document Number	**Rev**	**Description**
2000-F75-LST-EL-40001	C	FIM II & III TSF Electrical Load List
2000-F75-LST-EL-40002	0	FIM II & III TSF Electrical Equipment List
2000-F75-LST-EL-40003	C	FIM II & III TSF Cable Schedule
2000-F75-LST-IC-40003	C	FIM II & III TSF DCS List
Schematic Diagrams		
2000-F75-SCM-EL-40111	0	F75-CP-556 FIM III Underdrainage Pump 1 CP Schematic Diagram
2000-F75-SCM-EL-40112	0	F75-CP-557 FIM III Underdrainage Pump 2 CP Schematic Diagram
2000-F75-SCM-EL-40113	0	F75-CP-558 FIM III Toe Drain Pump CP Schematic Diagram
2000-F75-SCM-EL-40114	0	F75-CP-801 FIM III Seepage Pump 1 CP Schematic Diagram
2000-F75-SCM-EL-40115	0	F75-CP-802 FIM III Seepage Pump 1 CP Schematic Diagram
2000-F75-SCM-EL-40116	0	F75-CP-803 FIM III Seepage Pump 1 CP Schematic Diagram
2000-F75-SCM-EL-40117	0	F75-CP-804 FIM III Seepage Pump 1 CP Schematic Diagram
2000-F75-SCM-EL-40211	0	F75-CP-559 FIM II Cell G Toe Drain Pump 1 CP Schematic Diagram
2000-F75-SCM-EL-40212	0	F75-CP-560 FIM II Cell G Toe Drain Pump 2 CP Schematic Diagram
2000-F75-SCM-EL-40213	0	F75-CP-593 FIM II Cell G Underdrainage Pump CP Schematic Diagram
General Arrangement Drawings		
2000-F75-DRG-EL-40123	B	F75-CP-556 FIM III Underdrainage Pump 1 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40124	B	F75-CP-556 FIM III Underdrainage Pump 1 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40125	B	F75-CP-557 FIM III Underdrainage Pump 2 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40126	B	F75-CP-557 FIM III Underdrainage Pump 2 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40127	B	F75-CP-558 FIM III Toe Drain Pump Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40128	B	F75-CP-558 FIM III Toe Drain Pump Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40129	B	F75-CP-801 FIM III Seepage Pump 1 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40130	B	F75-CP-801 FIM III Seepage Pump 1 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40131	B	F75-CP-802 FIM III Seepage Pump 2 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40132	B	F75-CP-802 FIM III Seepage Pump 2 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40133	B	F75-CP-803 FIM III Seepage Pump 3 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40134	B	F75-CP-803 FIM III Seepage Pump 3 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40135	B	F75-CP-804 FIM III Seepage Pump 4 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40136	B	F75-CP-804 FIM III Seepage Pump 4 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40215	C	F75-CP-559 FIM II Cell G Toe Drain Pump 1 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40216	C	F75-CP-559 FIM II Cell G Toe Drain Pump 1 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40217	C	F75-CP-560 FIM II Cell G Toe Drain Pump 2 Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40218	B	F75-CP-560 FIM II Cell G Toe Drain Pump 2 Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40219	B	F75-CP-593 FIM II Cell G Underdrainage Pump Control Panel General Arrangement Sheet 1
2000-F75-DRG-EL-40220	B	F75-CP-593 FIM II Cell G Underdrainage Pump Control Panel General Arrangement Sheet 2
2000-F75-DRG-EL-40221	B	FIM II & III Local Control Station General Arrangement
Standard Drawings		
2000-F00-STD-EL-10005	1	Equipment Mounting Installation Details Sheet 1

Reference Specifications
2000-F00-STS-EL-10008_0 – Electrical Enclosures Specification 2000-F00-STS-EL-10014_2 - Preferred Equipment Suppliers for Electrical, Instrumentation and Controls Specification 2000-F00-STS-GE-10002_0 - Site Specific Information 2000-F00-STS-GE-10003_2 - Plant Numbering Specification 2000-F00-STS-ST-10001_2 - Steelwork Fabrication 2000-F00-STS-ST-10002_2 - Steelwork Erection Specification SPEC-00-G-05_12 – Technical Specification for Protective Coatings
Scope of Work
Work Included • Design, supply and fabrication of ten (10) pump control panels and six (6) local control stations including, but not limited to: o Form 1 Load Break Switch as specified on control panel general arrangement; o Pump MCCB(s) in control panels as required; o All internal Control Panel Components as specified in respective control panel general arrangement; o All internal wiring and cabling including power and control; o Labelling, including stainless steel equipment nameplate; o Lifting lugs, as applicable; o Any other items which are normally supplied with this equipment; • Surface Protection; • All ancillary items and special tools normally supplied with, or required to adjust and maintain all components associated with the equipment; • All fasteners, gaskets, packers, shims and any other items necessary for site assembly; • Factory Acceptance Testing at manufacturer's premises; • Supply of all necessary documentation, drawings and test documentation;
Work Excluded • Cabling external to control panel, local control station, and switchboard; • Spare parts; • Installation and commissioning at site

Description	Unit	Duty		Vendor	Notes	Rev
		Control Panels	LCS			
General						
Standard Specification		2000-F00-STS-EL-10008			1	A
Type Tested		Yes, provide certificates			1	A
Site Conditions		Refer to 2000-F00-STS-GE-10002 – Site Specific Information			1	A
Electrical System						
Earthing System		TN-S solidly earthed – Control Panel earth bar is connected to switchboard earth bar	N/A		1	A
Nominal Voltage	V	415 / 240 (+/- 6%)	N/A		1	A
Phases		3+N+E	N/A		1	A
Rated Frequency	Hz	50 (+/- 2%)	N/A		1	A
Environment Conditions						
Plant Location		Western Australia			1	A
Service Location	Indoor/ Outdoor	Outdoor			1	A
Site Data		Refer to 2000-F00-STS-GE-10002 – Site Specific Information			1	A
Panel Construction						
Applicable Standard		AS/NZS 61439			1	A
Enclosure Assembly		Metal clad, double skinned, single-sided			1	A
Ingress Protection		IP65			1	A
Mounting		Stand mounted in accordance with Detail 2 of standard drawing 2000-F00-STD-EL-10005	Column mounted in accordance with Detail 3 of standard drawing 2000-F00-STD-EL-10005		1	C
Connection		Front connected			1	A
Form of Internal Separation		1	N/A		1	B
Original Manufacturer (AS61439.1)					2	A
Assembly Manufacturer (AS61439.1)					2	A
Incomer Location					2	B
Extendable Board and Bus		Not Required			1	A
Spare Space		At least 20% of terminals and gland area			1	A
Cable Entry		Bottom entry			1	A
Current Rating Main Bus (3ph + N)	A	63A Main Isolator	N/A		1	A

Description	Unit	Duty		Vendor		Notes	Rev
		Control Panels	LCS				
Fault Current Rating	kA/sec	10kA/1sec	N/A			1	A
Current Rating Earth Bar	A					2	A
Busbar Configuration		NIL				1	A
Insulated Busbars		NIL				1	A
Enclosure							
Length - overall	mm	900	300			3	A
Depth – overall	mm	400	150			3	A
Height – minimum internal	mm	1200	300			3	A
Height – maximum external	mm	1230	330			3	A
Mass, including equipment	kg					2	A
Surface protection specification, colour		As per SPEC-00-G-05 – Technical Specification for Protective Coatings				1	A
Escutcheon (as required)		Gloss White	NIL			1	A
Weather Protection		Sloped roof	Weather shield			1	C

Notes
1. Fixed. The Vendor shall comply with this data, as a minimum. Vendor shall state their applicable ratings/data or compliance.
2. Vendor to Advise.
3. Preferred, Vendor to advise and provide reasoning for difference.

Vendor Drawing and Document Requirements List (VDDR)

E – Electronic Copy H – Hard Copy MDR – Manufacture's Data Report

FAT – Factory Acceptance Testing IOM – Installation and Operating Manual

VDDR			Required with Tender	Required after Award		As Built Required
			Copies	Copies	Weeks	Copies
A		**Production Schedule**				
	A01	Production Schedule / Bar Chart		1E	2	
	A02	Monthly Report		Monthly		
B		**Registers and General Drawing Requirements**				
	B01	Drawing Schedule / Register (Drawings Expected)		1E	2	
	B02	General Arrangement with Foundation Loads (in AutoCAD 2023 and PDF)				
	B03	Cross-section				
C		**Mounting and Erection Drawings**				
	C01	Foundation and Mounting Details (Provided in B02)				
	C02	Pipe Spools				
	C03	Outline Dimensions, Cut-out and Support Details (Provided in B02)				
	C04	Match Marked Erection Drawings				
	C05	Motor GA (with Fixing and Shaft Details, and Overall Dimensions)				
D		**Electrical Drawings (in electronic form as appropriate)**				
	D01	Single Line Diagrams				
	D02	Schematic Drawings				
	D03	Terminations / Loop Diagrams				
	D04	Panel Layout and Fabrication Details		1E	8	1E
	D05	Nameplate		1E	8	1E
	D06	Cable Block Drawings				
	D07	Switchboard GAs (Overall, Incomer and Module Type)		1E	8	1E
E		**Process and Piping Drawings**				
	E01	Process Flow Sheets				
	E02	Process and Instrument Diagram				
	E03	Pneumatic or Hydraulic Diagram				
	E04	Lubrication Diagram				
F		**Technical Data**				
	F01	Equipment Information Schedule				
	F02	Electrical Performance data sheet				
	F03	Equipment List				
	F04	Vendor's Surface Protection Details		1E	6	
	F05	Lubrication Data Schedule				
	F06	Material Schedule				
	F07	Bolt Schedule				
	F08	Fan Performance Curves				
	F09	Pump Performance Curves (with Duty Points Marked)				
	F10	Cable Schedule				
	F11	Vendor Catalogue Information	1E			
	F12	Calculations				
	F13	Completed $_{\text{Engineer}}$ Datasheets	1E			
	F14	Motor Datasheets				
	F15	Electrical Equipment List				
	F16	Instrument List				
	F17	I/O List				
	F18	Communications Addressing and Signal Mapping List				

VDDR			Required with Tender	Required after Award		As Built Required
			Copies	Copies	Weeks	Copies
G		**Inspection, Certification and MDR**				
	G01	Inspection and Test Plans		1E	6	
	G02	Inspection and Test Procedures (generic)				
	G03	Quality Plans and Procedures (generic)		1E	4	
	G04	Manufacturer's Data Report (MDR) – Index / Contents		1E	4	
	G05	Manufacturer's Data Report (MDR)		1E	Delivery -4	
	G06	Material Certificates		In MDR		
	G07	Statutory Authority Certificates		In MDR		
	G08	Test Data and Other Certificates		In MDR		
	G09	Welding Procedure / Specification				
	G10	Non-Destructive Testing (NDT) Procedures				
	G11	Material Safety Data Sheets				
	G12	Commissioning Plan and Procedure		1E	Delivery - 4	
	G13	Structural Design Certification				
	G14	Performance Guarantee Statement				
H		**Shipping and Packing Details**				
	H01	Material / Shipping List	1E	1E	Delivery -4	
	H02	Package Type and Quantity (Carton, Case, Crate)		1E	Delivery -4	
	H03	Shipping Packages – Weights and Dimensions		1E	Delivery -4	
	H04	Shipping and Handling Procedure		1E	12	
J		**Manuals**				
	J01	Installation, Operation and Maintenance Manual (Preliminary)		1E	Delivery -4	
	J02	Installation, Operation and Maintenance Manual (Final)		1E	Delivery	
K		**Spare Parts Information**				
	K01	Spare Parts Catalogue and Recommended Spares List (Copy also in Manuals)	1E	1E	8	
	K02	Recommended Spare Parts List with Pricing (Not Included in Manuals)	1E	1E	Prelim 4 Delivery +1	
	K03	Special Tools list	1E	1E	8	
M		**General**				
	M01	Control Philosophy and Logic Diagram				
	M02	Functional Description				